



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

Shereen Winda

Shereen Winda

316 S Curry St

Hampton, VA

United States

sdw820@yahoo.com

Estimate Number: 1422

Estimate Date: September 30, 2026

Valid Until: October 7, 2026

Grand Total (USD): \$3,550.00

- | | |
|---|---|
| 1. Dehumidifier — AprilAire E100 (1 ea): supply and install an AprilAire E100 crawl space dehumidifier with its companion condensation pump, so the unit pulls the moisture out of the air and the pump moves that water up and out of the crawl space. | 1 |
| 2. Electrical Outlet — dedicated circuit (1 ea): a dedicated GFI outlet on its own breaker to power the dehumidifier, installed by a licensed electrician, including the electrical permit and inspection. | 1 |
| 3. Repin & Re-Hang the Floor Insulation — 1 job: the fallen floor insulation is pinned back up and re-hung in the joist bays across the crawl space; existing insulation only. | 1 |
| 4. Mortar the Loose Brick — 1 job: the loose brick in the foundation wall is pointed up and mortared back into the wall so the opening is closed and the wall is sound. | 1 |

Grand Total (USD): **\$3,550.00**

Notes / Terms

NOT INCLUDED: any clean-out or debris removal; any new insulation (batts are customer-supplied); vapor barrier or encapsulation work; drainage, sump or exterior waterproofing; structural repair (beam, piers, joists, subfloor); mold or fungus treatment; sealing the foundation vents; crawl space doors; any work not listed in the scope above.

Notes:

**Jobsite will be left clean once completed.

**Contractor is not responsible for damage caused inside the home while working in the crawl space.

Warranty:

**12 months workmanship on the work performed; 5 years on the dehumidifier.

Payment Terms:

Total Project Cost: \$3,550.00

Deposit to Schedule: \$1,775.00



Final Payment: \$1,775.00

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Questions on this estimate: Jeff Wilson — text or call 757-322-7171

Validity: valid until October 7, 2026.



SCOPE OF WORK

1. Dehumidifier — AprilAire E100 with its condensation pump, supplied and installed;
2. Electrical Outlet — dedicated GFI circuit and outlet on its own breaker for the dehumidifier, licensed electrician, permit and inspection included;
3. Repin & Re-Hang the Floor Insulation — the fallen floor insulation is pinned back up in the joist bays;
4. Mortar the Loose Brick — the loose brick in the foundation wall is pointed up and mortared back in.

JOB DESCRIPTION

The floor insulation in the crawl space has come loose and is hanging down out of the joists, the air down there is holding moisture, and there is a loose brick in the foundation wall. This estimate puts the insulation back up where it belongs across the crawl space, installs an AprilAire E100 dehumidifier with its condensation pump together with the dedicated outlet that powers it, and mortars the loose brick back into the wall.

View your full scope of work online: <https://tidewater-est-316-s-curry.pages.dev>

Questions on this estimate: Jeff Wilson — text or call 757-322-7171